

Designers Risk Assessments

Project Name	Priory Primary School	Project ID	2-205-4
Designer's Name	Ken Carmichael	Date	27/09/2006

Activity Name	SIPS wall Paneling	Risk Level	High
The use of and fixing of a super insulated panel as the inner leaf to the external wall and internal wall construction.			
Hazards			
Falls of materials onto other persons, persons falling, working at height.			
Persons at Risk			
Site Staff Visitors Contractors Third Party Panel Fixers			
Measures to reduce risk			
All work to be planned and all necessary risk assessments and method statements to be undertaken prior to commencing work on site. No work to be undertaken above persons working below, contractor to restrict access to this area. Contractor to use suitable access equipment. Contractor to ensure that the frame and paneling system are fully integrated to ensure stability of the structure. Contractor to ensure that all lifting operations comply with the lifting regulations 1998.			

Activity Name	Roof tiling	Risk Level	High
Supply and fix of roof tiling, battening and felt			
Hazards			
Falls of materials onto other persons, persons falling, awareness of crane for placing of the tiling on the structure. Working at height.			
Persons at Risk			
Site Staff Visitors Roofers Contractors Third Party			
Measures to reduce risk			
All work to be planned and all necessary risk assessments and method statements to be undertaken prior to commencing work on site. No work to be undertaken above persons working below, contractor to restrict access to this area. Contractor to use suitable access equipment. Contractor to ensure that all lifting operations comply with the lifting regulations 1998. No materials to be left unsecured at high level at any time.			

Activity Name	Internal jumbo stud partitioning	Risk Level	High
Hazards			
Falls of materials onto other persons, persons falling, working at height. Manual handling issues.			
Persons at Risk			
Site Staff Visitors Contractors Third Party Installers General Public			
Measures to reduce risk			
All work to be planned and all necessary risk assessments and method statements to be undertaken prior to commencing work on site. No work to be undertaken above persons working below, contractor to restrict access to this area. Contractor to use suitable access equipment. Contractor to ensure that all lifting operations comply with the lifting regulations 1998. No persons to lift plasterboard panels onto studs.			

Activity Name	Manual handling	Risk Level	Medium
Handling of heavy goods and materials			
Hazards			
Lifting heavy materials etc.			
Persons at Risk			
Contractors Roofers Installers General Site Operatives Window Installers Panel Fixers			
Measures to reduce risk			
Ensure site operatives have been trained in manual handling lifting operations. All lifting of heavy materials and equipment to be undertaken by mechanical means.			